

## Hampshire County Health Department

HC 71, Box 9 Augusta, WV 26704

Nursing: (304) 496-9640 Environmental: (304) 496-9641 Fax: (304) 496-9650

November 3, 2006

Hampshire County Planning Commission PO Box 883 Romney, WV 26757

Dear Sirs:

This office has reviewed a plat of survey for WV Hunter, LLC to approve a subdivision called Bluffs on the Potomac Section 5 located on Graces Cabin Road, and further referenced as Tax District Romney, Tax Map 33, Parcel 3, Deed book 436, Page 638. This subdivision section consists of 33 lots containing 783.76 acres. All lots contain a sewage disposal area of 10,000 square feet where no development or structures other than the septic system shall be permitted. These lots are to be developed with individual wells and septic systems to serve single family dwellings.

Percolation test results are within limits as set forth by West Virginia CRS 16-1. Six foot soil observation holes indicate no restrictions due to water table or shallow bedrock within the designated sewage disposal area except as noted on the Health Department subdivision application.

The plats of survey dated 6/25/06, is hereby approved by the Hampshire County Health Department. Any changes or revisions to the Health Department stamped and signed plat, or subsequent final plats approved based upon the approved plat, will make this approval null and void.

This approval is not permit for individual water systems or individual sewer systems. Applications for permits must be made separately to the Hampshire County Health Department.

Sincerely,

Terry Mayhew, RS

CC: WV Hunter, LLC

Eur AMayle

section # 5

## REPORT SHEET FOR PERCOLATION AND SIX FOOT HOLE TESTING

Subdivision Name Bluffs on the Patamaccounty Hampshire
Total Number of Lots Name of Applicant
Name of Certified Installer Responsible for Testing Justin Time Etc.
Installer Certification No Installer Signature Signature
Address HC Ley Box 1624 Romney W.U. 2007 57

Type System	Lot Number	Percolation	Tout Requite	(Minutes per l	inch of Fam	Average Results	Six Foot H	Date Conducted	
		35	30	40	125	5:4	NA	Depth to Rock  A∫A	4/1/06
#	.113	45	48 .	40	38	7.1	j j		
I	114	28	20	48	35	5.4			
	115	55	55	30	45	7.7			
I	116	95	80	75	100	14.5			<u> </u>
I	117	150	170 _	190 _	165	28.1			
I	118	190	100	198	205	28.8			<u> </u>
工	119	190	215	195	205	33.5			<u> </u>
II	120	55	60	68	55	10.3			
1	121	55	40	60	45	8.3			
I	laa	60	65	60	55	10.0			
I	123	65	30	35	40	7.0			1
I	124	68	70	75	60	11.5			
工	195	60	70	75	65	11.2			
II	126	45	40	60	50	8.1			
II	127	70	74	76	60	11.6			+
I	198	80	85	40	30	9.7			
I	1129	70	70	30	60	9.5			1
11	130	65	70	35	40	8.7	180		1
TI	131	45	30	60	50	7,7			LV

(Attach additional pages if needed)

peac tests Approved by Donson Talkata
4/19020/06
5/10430/06

ction #5

## REPORT SHEET FOR PERCOLATION AND SIX FOOT HOLE TESTING

Subdivision Name Bloff	s on the Potomac county Hampshine
Total Number of Lots	Name of Applicant
Name of Certified Installer R	Responsible for Testing Justin Time Exc
54 Installer Certification No	Installer Signature Lary Mullin
,	Address HC 64 Box 1634 Romney, W. V. 26757

Type System	Lot Number	Percolation Test Results (Minutes per Inch of Fall)				Average Results	Six Foot Hole Results  Depth to Water Depth to Rock		Date Conducted	
							NA.	AA	4/1	106
		90_	70	80	90		_ IAH	1	"	1
#	133	80	30	60	40	8.7			-	
T	, 134	100	.80	60	190	11.2			-	
#	135	(60)	30	190	50	9.5				-
#	136	100	90	60	80	12.0			-	+-
#	137	80	90	70	130	15.0			-	+
	10000	50	55	100	60	11.0			-	4
<u> </u>	138	<i>8</i> S	120	120	160	16.0			-	_
<u> </u>	139			100	95	14.3				-
工	140	90	80	88	75	10.5				
IL	141	100		80	120	11.6				
I	142	100	70			12.9				
II	143	80	90	100	40				1	$\sqrt{}$
II	144	60	80	95	100	13.9	1			-
			10			-		-		
			•				-		_	
									+	
					4					
f	-		ar ar						_	
									+	
		-		-						-

(Attach additional pages if needed)

Pencolation tests Approved by Denson Taketa 4/19420/06 5/10430/06